

ADDENDUM NO. ONE (1)

TO
THE CONTRACT DOCUMENTS
FOR THE

Ground Storage Tank Inspection Project

IN
HERNANDO COUNTY, FLORIDA
SOLICITATION NO. 23-ITB00285

BID DUE DATE: June 19, 2023

NOTICE

BIDDERS ARE REQUIRED TO ACKNOWLEDGE RECEIPT OF
THIS ADDENDUM BY THE TIME OF THE BID DATE.

TO ALL PLAN HOLDERS:

The following changes, additions and/or deletions are hereby made a part of the Contract Documents for the Ground Storage Tank Inspection Project, located in Hernando County, as fully and completely as if the same were fully set forth therein:

A. CLARIFICATIONS

1. **Question:** Can commercial divers be utilized to clean, inspect, and perform capable maintenance while tanks remain full of water?
Answer: No.
2. **Question:** How much and what type of sediment is to be expected inside each tank?
Answer: In past inspections there were four GST (Southwest X 2, Cartee and Eldridge) with approximately 3 to 5 yards of sand in them. In the Seville GST there was some delamination of the concrete from the interior floor and walls and sand, approximately 1 to 3 yards. The Jamaica GST will have an iron sludge in it that must be pumped out with a sump pump. The rest of the GST had approximately 1 to 3 yards of sand.
3. **Question:** Can the sediment removed during cleaning services be released on-site near each tank's location?
Answer: Yes.
4. **Question:** Will the contractor be responsible for any off-site disposal?
Answer: No, the County will remove the debris/material from the sites.
5. **Question:** Are there any baffle walls in any of the water tanks? If so, which ones?
Answer: No baffles. Just a small mixer in the Seville GST. It will not interfere with the cleaning of the tank.

BOARD OF COUNTY COMMISSIONERS
HERNANDO COUNTY

A handwritten signature in blue ink, appearing to read "Toni Brady", is written over a solid black horizontal line.

for: Toni Brady
Chief Procurement Officer, Hernando County

Issued: May 31, 2023