

ADDENDUM NO. One (1)

TO
THE CONTRACT DOCUMENTS
FOR THE

Spring Hill Water Reclamation Facility Demolition

IN
HERNANDO COUNTY, FLORIDA
SOLICITATION NO. 23-C00051/GL

NOTICE

BIDDERS ARE REQUIRED TO ACKNOWLEDGE RECEIPT OF
THIS ADDENDUM IN OPENGOV PROCUREMENT

The following changes, additions and/or deletions are hereby made a part of the Contract Documents for the **SOLICITATION NO. 23-C00051/GL**, as fully and completely as if the same were fully set forth therein:

A. CLARIFICATIONS

1. Exhibit "C" Technical Specifications section 1.3.1.4 and associated subsections are modified to include the italicized and underlined language:

1.3.1.4 Remove above ground and below ground structures, per FDOT Sections 110, 120, and the specifications within (see exhibit D). Structures to include:

1.3.1.4.1 All building structures, including foundations (slabs, footers, and column supports) to a minimum of two (2) feet below existing grade and use markers to identify location of structures.

1.3.1.4.2 All above ground water and wastewater piping, appurtenances, and fittings, and all electrical runs, to a minimum of two (2) feet below existing grade at the point of ground entry and use markers to identify location of structures. Underground piping and conduit buried beyond the two (2) foot threshold shall be capped and abandoned in place

1.3.1.4.3 All manholes and wet wells shall be removed in their entirety. Resulting excavations shall be backfilled to existing grade.

1.3.1.4.4 Plant head works, clarifiers, oxidation ditch, chlorine contact chamber, aerobic digester, reaeration tanks, sludge thickener, and any other 3 structures shown in document Exhibit B to a minimum of two (2) feet below existing grade and use markers to identify location of structures.

2. Exhibit "C" Technical Specifications section 1.3.1.9 is modified to read:


1.3.1.9 Demo onsite ~~monitoring and~~ potable wells.

3. Exhibit "C" Technical Specifications page 7 is modified to remove bullet point two:

- ~~There is a monitoring well located about 50 ft west of building 11 that will need to be abandoned.~~

4. Exhibit "C" Technical Specifications page 15 "Items To Be Kept By HCUD OPERATIONS: is modified to include the stairwell and five (5) quick connects shown in the pictures attached to this addendum.

BOARD OF COUNTY COMMISSIONERS
HERNANDO COUNTY



for: Toni Brady
Chief Procurement Officer, Hernando County

Acknowledged

Issued: April 21, 2023



HCUD will be keeping these stairs. If they are still there during demo, set to the side and contact PM for removal

2nd view of the stairs
being kept by HCUD





HCUD will be keeping the 5 quick connects that are circled.