REFERENCE SURVEY CONTROL

1. HORIZONTAL CONTROL WAS ESTABLISHED BY REFORMING/SEVERAL TIMES KINEMATIC (RTK)/GLOBAL POSITIONING SYSTEM (GPS) OBSERVATIONS OF ANYMINUM OF TWO SEPARATE THREE MINUTE OBSERVATIONS.
2. VERTICAL CONTROL WAS ESTABLISHED BY GPS OBSERVATIONS RELATIVE TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88)
3. BEARINGS SHOWN ON THIS SURVEY ARE BASED ON THE EAST LINE OF THE SOUTHEAST [OF SECTION 20, TOWNSHIP 22 SOUTH, RANGE 18 EAST, HERNANDO COUNTY, FLORIDA HAVING A BEARING OF SOUTH 00°16'05" EAST, ALL OTHER BEARINGS ARE RELATIVE TO SAID LINE.
4. RELATIVE HORIZONTAL AND VERTICAL ACCURACIES OF THESE FEATURES SHOWN ARE ESTIMATED TO BE 0.2' ± BASED ON TOTAL STATION TYPE ONOMETRIC METHODS AND REAL TIME KINEMATIC GPS METHODS.
5. THE FEATURES SHOWN HEREON ARE REFERENCED TO AN NORTH ANGLED UPON THE NORTH AMERICAN HORIZONTAL DATUM OF 1983 (NAD 83) 2011 ADJUSTMENT, FLORIDA WEST ZONE, REFERENCED TO THE FLORIDA PERMANENT REFERENCENETWORK.
6. ALL CONTROL MEASUREMENTS EXCEEDED CLOSURES OF COMMER CIAL MINIMUM R LINEAR, 1 FOOT IN 10,000 FEET.

SURVEYOR'S NOTES

1. SURVEY DATA ACQUISITION WAS PERFORMED BY LANGAN ENGINEERING AND ENVIRONMENTAL SERVICES WITH A LAST DAY OF ACQUISITION ON MAY 10, 2022. INITIAL SURVEY DATA CONSTRUCTIONS AND ANALYSIS WERE COMPLETED ON FOR SURVEY 14, 2022.
2. ALL SYMBOLS USED TO DEPICT IMPROVEMENTS ARE NOT TO SCALE
3. THIS MAP IS INTENDED TO BE DISPLAYED AT A SCALE OF 1"=40' ON BMLLER, UNLESS OTHERWISE NOTED. LINEAR UNITS SHOWN ARE U.S. SURVEY FEET.
4. TYPE OF SURVEY: ALTA/NSPS LAND TITLE SURVEY PER CHAPTER 5J-17 F.A.C. USE OF THIS SURVEY FOR PURPOSES OTHER THAN WHICH IT WAS INTENDED, WITHOUT WRITTEN CONSENT FROM, WILL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO THE SURVEYOR. NOTHING HEREIN WILL RECONSTRUED TO GIVE ANY RIGHTS OR BENEFIT S TO ANYONE OTHER THAN THOSE CERTIFIED TO
5. THERE ARE NO VISIBLE INSERENT GAPS, GORES OR WAYS TO THE SURVEYED PROPERTY.
6. THE STREET AD DRESS OF THIS SUBJECT PROPERTY IS 12338 PINE CONE STREET, BROOKSVILLE, FL 34613.
7. ACCESS TO THE SUBJECT PROPERTY IS FROM PUBLICLY DEDICATED RIGHT-OF-WAY KNOWN AS PINE GROVE BOULEVARD, AS SHOWN ON THE PLAT OF PINE GROVE SUBDIVISION UNIT 1, PLAT BOOK 15, PAGE 98, AS RECORDED IN THE PUBLIC RECORDS OF HERNANDO COUNTY, FLORIDA, AND FROM PINE CONE STREET WHICH IS A 50 FOOT RIGHT-OF-WAY AS SHOWN ON THE PLAT OF PINE GROVE SUBDIVISION UNIT 2, PLAT BOOK 15, PAGE 99, AS RECOR DED IN THE PUBLIC RECORDS OF HERNANDO COUNTY, FLORIDA AND FROM A NONDEDICATED ROADWAY KNOWN AS EMMA ROAD, AND A 20.0 FEET WIDE ACCESS EASEMENT ACROSS THE NORTH 20 FEET OF BLOCK B, LOT 1, OF THE PLAT OF PINE GROVE SUBDIVISION UNIT 2, PLAT BOOK 15, PAGE 99, AS RECORDED IN THE PUBLIC RECORDS OF HERNANDO COUNTY, FLORIDA.
8. ALL ADJOINING RIGHTS-OF-WAY, SUBDIVISIONS AND INFORMATION ON ADJOINING PROPERTIES SH OWN HEREON WERE OBTAINED FROM PUBLIC RECORDS AND/OR FIELD OBSERVATIONS. USE OF THIS SURVEY ARE PLACED ON NOTICE THAT RELIANCE ON SUCH INFORMATION IS AT THEIR OWN RISKS., IN THIS REGARD:
9. THIS SURVEY DOES NOT DETERMINE FENCE AND/OR WALL OWNERSHIP
10. THIS SURVEY D OES NOT MAKE ANY REPRESENTATIONS TO ZONING OR DEVELOPMENT RESTRICTIONS OR LAND S ADJACENT TO THIS SURVEYED LINES.
11. THIS SURVEY WAS PREPARED WITH THE BENEFIT OF ALAND TITLE COMMITMENT IS SUED BY OLD REPUBLIC NATIONAL TITLE INSURAN CE COMPANY WITH A COMMITMENT DATE OF DECEMBER 14, 2021 AND REVISED ON FEBRUARY 11, 2022.
12. THIS S URVEY ONLY REFLECTS MATTERS SHOWN ON THE TITLE COMMIT MENT ISSED BY OL D REPUBLIC NATIONAL TITLE INSURANCE COMPANY WITH A COMMIT MENT DATE OF DECEMBER 14, 2021 AND REVISED ON FEB RUARY 11, 2022, AND D OES NOT REFLECT ANY OTHER MATTERS OF RECORD NOT SET FORTH IN SUCH COMMITMENT.
13. UNRECORDED EASEMENTS OR RES TRICTIONS OF RECORD OTHER THAN THOSE SHOWN HEREON M AY EXIST. THERE MAY BE EASEMENTS RECORDED IN THE PUBLIC RECOR DS NOT SHOWN UPON THIS SURVEY.
14. NO EXCAVATIONS WERE PERFORMED TO VERIFY THE LOCATION OR EXISTENCE OF ANY UNDERGROUND IMPROVEMENTS. S TRUCTURES, OR FOUNDATIONS UNDER GROUND UTILITIES SHOWN HEREON ARE SHOWN PER ABOVE GROUND EVIDENCE ONLY. D RAINAGE AND SEWER PIPES USED WERE NOT PULLED FROM V IELD OBSERVATIONS OF MANHOLES AND/OR INLETS. THE SIZE AND LOCATION OF UNDERGROUND FEATURES CANNOT BE RELIED UPON THEREFORE IS NOT CERTIFIED BY THIS SURVEY. INVER T ELEVATIONS MAY VARY WHEN PIPE OPENING S INACCESSIBLE. THIS DOCUMENT S HOULD NOT BE RELIED UPON FOR EXCAVATION OR ON TOTAL DESIGN PURPOS ES WITHOUT FIELD VERIFICATION OF UNDERGROUND UTILITY LOCATIONS. UTILITIES OTHER THAN THOSE SHOWN HEREON MAY EXIS T UNLESS OTHERWISE NOTED. THIS FIRM WAS NOT ATTEMPTED TO LOCATE UNDERGROUND UTILITIES SUCH AS GAS LINES, UTILITIES, FASTINGS, ANDOR FLEXIBLE CONDUITS WHICH MAY OR MAY NOT HOUSE CABLE OR EASEMENT LINES.
15. THE TREES IDENTIFIED AND SHOWN ARE IN PROXIMITY TO BE CONSIDERED A TREE SURVEY. T REE SYMBOLS REPRESENT THE LOCATION OF THE CENTER OF THE TR UNK AND DO NOT REPRESENT THE TRUE E OF THE CANOPY. SIZE OF THE TREHE IS PECIFIED IS THE DIAMETER OF THE TRUNK, IN INCHES, AT BREAST HEIGHT. TREES ARE NOT LOCATED BY FIELD SURVEY UNLESS SPECIFICALLY STATED IN THE SURVEY NOTES AND THEREFORE IS NOT CERTIFIED BY THIS SURVEY. CONTACT WITH AN ARBORIST FOR EXACT SIZE, CLASSIFICATION.
16. ENVIRONMENTAL AND/OR HAZARDOUS MATERIALS LOCATION, IF ANY, ARE NOT COVERED UNDER THIS SURVEY. NO ENVIRONMENTAL ISSUES H AVE BEEN ACC REDDED BY THIS SURVEY
17. CONTOUR LINES AND SPOT ELEVATIONS SHOWN ON THIS SURVEY ARE DERIVED FROM A DIGITAL ELEVATION MODEL GE NERATED FROM AERIAL LIDAR DATA COLLECTED ON JULY 9, 2021 WITH AN ESTIMATED PRECISI ON OF +/- 0.5 FEET.
18. THERE WAS NO EVIDENCE OF ACTIVE CONSTRUCTION ACTIVITIES OBSERVED DURING THE PROCESS OF CONDUCTING FIELD WORK.
19. NOCONDITIONS WERE ENCOUNTERED THAT PREVENTED FLORIDA AND MINES YSM VIN. CODE 5J-17 FROM BEING MET.
20. THE WORD "CERTIFY" OR "CERTIFICATION" AS EMPHASIZED USED HEREON, MEANS AN EXPRESSION OF PROFESSIONAL OPINION REGARDING THE FACTS OF THIS SURVEY AND DOES NOT CONSTITU TE A WARRANTY OR GUARANTEE, EXPRESSED OR IMPLIED.
21. ADDITIONS OR DELETIONS T O THIS MAP AND REPORT BY OTHER THAN THE SIGNING PARTY OR PARTIES IS PROHIBITED WITHOUT WRITTEN CONSENT OF THE SIGNING PARTY OR PARTIES
22. THIS SURVEY IS NEITHER FULL NOR COM PLETE WITHOUT ALL S HEETS OF THIS SET.
23. HIGHWAY EASEMENT DESCRIBED IN DEED BOOK 23, PAGE 97, CO NTY PUBLIC RECORDS OF HERNANDOCOUNTY, FLORIDA, HAS BEEN EXTINGUISHED PURSUANT T O THE MARKETABLE RECORD TITLE ACT, CHAPTER 5 77.07 (2)(B)(3), STATUTES, AS EVIDENCED BY AFFIDAVIT RECORDED IN OFFICIAL RECORDS BOOK 4766, PAGE 1885, OF THE PUBLIC RECORDS OF HERNANDO COUNTY, FLORIDA.

TITLE REPORT

AMERICAN LAND TITLE ASSOCIATION COMMITMENT F OR TITLE INSURANCE ISSUED BY OLD REPUBLIC NATIONAL TITLE INSURANCE COMPANY

FILE NUMBER: 2200629
ISSUING OFFICE FILE NUMBER: 4563.1775
COMMITMENT DATE: DECEMBER 14, 2021 AT 8:00 AM
REVISED DATE: FEBRUARY 11, 2022 AT 12:37P M.

SCHEDULE B SECTION II:

ITEMS 1-4 ARE NOT SURVEY RELATED
5. EASEMENTS OR CLAIMS OF EASEMENTS NOT SH OWN BY THE PUBLIC RECOR DS
6. GENERAL OR SPECIAL TAXES AND ASSES SMENTS REQUIRED TO BE PAID IN THE YEAR 2022AND SUB SEQUENT YEARS. (NOT SURVEY RELATED)
7. ANY LIEN PR OVIDED BY COUNTY ORDINANCE OR BY CH 159, F.S., IN FAVOR OF ANY CITY, TOWN, CITY OF BROOKSVILLE, OR SPECIAL TAX DISTRICT, UNLESS THE LAND DESCRIBED IN SCHEDULE A (OR 2(A) OR 2(B), IS WITHIN A DULY CREATED AND EXISTING TAXI ANDDES CRIBED HEREIN, AND ANY LIEN FOR WHICH TITLE IS IN FAVOR OF ANY COUNTY OR MUNICIPALITY. (NOT SURVEY RELATED)
8. SUBJECT TO DRAINAGE RIGHTS OF WAY AS many PRESENTLY EXIST. (AS SHOWN ON SURVEY)
9. NOTWITHSTANDING THE INSURING PROVISIONSUNDER COVERED RISK 4 OF THE JACKET OF THIS POLICY, THIS POLICY DOES NOT INSURE ANY RIGHT, [IF ACCESS TO AND FROM SAID LAND, [NOTE: ACCESS TO AND FROM SAID LAND IS NOT INSURED AS A FUNCTION OF A NEW PLAT BASED ON THE PLAT, SET FORTH HEREIN] (AS SHOWN ON SURVEY)
10. RIGHT S OF TENANTS AND/OR PARTIES IN POSSESSION, AND ANY PARTIES CLAIMING, BY THROUGH OR UNDER S AS TENANTS OR PARTIES IN POSSESSION, AS TO ANY UNRECORDED LEASES OR RENTAL AG REEMENT S. (NOT SURVEY RELATED)
11. ALL MATTERS CONTAINED ON THE PLAT OF PINE GROVE SUB DIVISION UNIT 2, AS RECOR DDED IN PLAT BOOK 15, PAGES 99. (SHOWN ON SURVEY)
12. OIL, GAS, MINERAL, OR OTHER RESERVATIONS AS SET FORTH IN DEED RECORDED IN DEED BOOK 23, PAGE 97, AND AS AFFECTED BY THE MARKETABLE RECORD TITLE ACT, CHAPTER 5 77.07 (2)(B)(3), CURRENT RECORD OWNER F OR THEN-TO-BE-IDENTIFIED HEREIN. THE RIGHTS OF ENTRY AND DRILLING OPERATION WHICH MIGHT BE RELATED ORSU MMARIZED OF RECORD. (NOT S URVEY RELATED)
13. INTENTIONALLY DELETED
14. RIGHT S OF TENANTS AND/OR PARTIES IN POS SESSION, AND ANY PARTIES CLAIMING, BY THROUGH OR UNDERS AS TENANTS OR PARTIES IN POSSESSION, AS TO ANY UNRECOR DED LEASES OR RENTAL AGREEMENTS. (NOT SURVEY RELATED)

LEGAL DESCRIPTION

PARCEL 1

THE SOUTH 661.00 FEET OF THE WEST [OF THE NOR THEAST [OF THE SOUTHEAST] OF SECTION 20, TOWNSHIP 22 SOUTH, R ANGE 18 EAST, HERNANDO COUNTY, FLORIDA.

TOGETHER WITH AN INGRESS AND AGRESS EASEMENT OVER THE NORTH 20.00 FEE TOF LOT 1, BLOCK B, PINE G ROVE SUBDIVISION UNIT 2, ACCORDING TO MAP OR PLAT THEREOF RECORDED IN PLAT BOOK 15, PAGE 99, PUBLIC RECORDS OF HERNANDO COUNTY, FLORIDA.

AND

THE WEST [OF THE NORTHEAST [OF THE SOUTHEAST [OF SECTION 20, TOWNSHIP 22 SOUTH, RANGE 18 EAST, HERNANDO COUNTY, FLORIDA LESS THE SOUTH 661.00 FEET THEREOF.

PARCEL 2

THE NORTH 661 ' [OF THE SOUTHEAST [OF SECTION20, TOWNSHIP 22 SOUTH, RANGE18 EAST, HERNANDO COUNTY, FLORIDA

LEGEND AND ABBREVIATIONS

(NOT SHOWN TO SCALE)

- IRON PIPE (FOUND/SET)
- IRON ROD FOUND
- NAIL & WASHER (FOUND/SET)
- MONUMENT (FOUND/SET)
- SECTION CORNER
- QUARTER CORNER
- PIN AND CAP (FOUND/SET)
- REBAR (FOUND/SET)
- FLAG POLE
- MAILBOX
- AIR CONDITIONING UNIT
- LIGHTING FIXTURE
- LIGHT POLES
- ASPHALT PAVEMENT
- BRICK PAVERS
- BUILDING — BUILDING OVERHANG
- CONCRETE
- SUBDIVISION BOUNDARY
- SUBDIVISION LINES
- EASEMENT BOUNDARY
- PROPERTY BOUNDARY
- ADJOINING PROPERTY BOUNDARY
- RIGHT OF WAY LINE
- OVERHEAD WIRES
- WIRE FENCE
- CHAIN LINK FENCE
- MAJOR CONTOUR INTERVAL
- MINOR CONTOUR INTERVAL
- WATER EDGE
- TREE/HEDGE LINE
- LANDSCAPING EDGE
- UTILITY POLE
- GUY ANCHOR
- GUY POLE
- FENCE POST
- UTILITY BOX/PEDESTAL (AS IDENTIFIED)
- UTILITY METER (AS IDENTIFIED)
- UTILITY MARKER
- UNDERGROUND VAULT
- CATCH BASIN
- MANHOLE (AS IDENTIFIED)
- UTILITY VALVE (AS IDENTIFIED)
- FIRE HYDRANT
- CLEANOUT
- PALM TREE
- DECIDUOUS TREE
- CONIFEROUS TREE
- SHRUB
- STUMP
- SIGN
- GATE

ENG.	ENGINEERING
P	PLAT BEARING/DISTANCE
(M)	MEASURED BEARING/DISTANCE
P.O.B.	POINT OF BEGINNING
P.O.C.	POINT OF COMMENCEMENT
R/W	RIGHT-OF-WAY
R	RANGE
SEC.	SECTION
T	TOWNSHIP
S.F.	SQUARE FEET
LB	LICENSED BUSINESS
D.B.	DEED BOOK
F.A.C.	FLORIDA ADMINISTRATIVE CODE
No.	NUMBER
O.R.B.	OFFICIAL RECORD BOOK
PG	PAGE
P.B.	PLAT BOOK
DR	GRATED INLET
INV	INVERT ELEVATION
PVC	POLYVINYL CHLORIDE PIPE

PROJECT LOCATION MAP
SCALE: NOT TO SCALE

SURVEYOR'S CERTIFICATION

TO:
a. OAK DEVELOPMENT GR OUP LLC
b. OAK BROOKSVILLE LLC
c. WILLIAM J. KEMP, ON, P.A.
d. OLD REPUBLIC NATIONAL TITLE INSURANCE COM PANY
e. WILLIAM RY AN HOMES FLORIDA, INC
f. WILLIAM RY AN HOMES, P.A.
g. TAMPA PINES, LLC
h. **TAMPA PINES II, LLC**
i. SUCHES T MAKA, ITS SUCCESSORS AND/OR ASSIGNS

THISSE TO CERTIFY TH AT THIS MAP OR PLAT AND THIS SURVEY ON WHICH IT IS BASED WERE MADE IN ACCORDANCE WITH THE 2021 MINIMUM STANDARD DETAIL REQUIREMENTS FOR ALTA/NSPS LAND TITLE SURVEYS JOINTLY ESTABLISHED AND ADOPTED BY ALTA AND NSPS, AND INCLUDES ITEMS 1, 2, 3, 4, 7(a), 7(b)(1), 7(c), 8, 9, 10(a), 11(a), 13, 14, 16, 17, 18, 19 AND 20(a) OF TABLE A THEREOF. THE FIELD WORK WAS COMPLETED ON [redacted]

DATEOF PLAT OR MAP: SEE TITLE BLOCK FOR DATEOF LATEST REVISION

GARY M. MCDANIEL
PROFESSIONAL SURVEYOR AND MAPPER
LICENSE NUMBER 6 5787
STATE OF FLORIDA, DEPARTMENTOFENVIRONMENTAL SERVICES, INC
LICENSED BUSINESS NUMBER LB6170, STATE OF FLORIDA

THISFEATURES SHOWN ON THIS SURVEY ARE VALID AS TO THE DATE OF THE LAST FIELD WORK, NOT TO THE SIGNATURE DATE OF THIS CERTIFICATION

THIS DOCUMENT HAS BEEN DIGITALLY SIGNED AND SEALED BY THE ABOVE NAMED PROFESSIONAL SURVEYOR AND MAPPER USING A DIGITAL SIGNATURE AND DIGITAL CERTIFICATE

PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED. THE AUTHENTICATION CODE MUST BE VERIFIED ON ALL ELECTRONIC COPIES

No.	Revisions	Date
2	ADDED TREES & CERTIFICATION	5/17/2022
1	ADDED CERTIFICATIONS	5/05/2022

LANGAN
Langan Engineering and Environmental Services, Inc.
400 N. Ashley Drive, Suite 2175
Tampa, FL 33602
T: 813.429.8100 F: 813.429.9101 www.langan.com
FL CERTIFICATE OF AUTHORIZATION NO. 00000151/LB0712LANGAN

Project: OAK GROUP - PINE CONE STREET
BROOKSVILLE HERNANDO COUNTY FLORIDA

Drawing Title: ALTA/NSPS LAND TITLE SURVEY

Project No.: 350035301
Date: 04/20/2022
Drawn By: CM
Checked By: DAN

Drawing No.: EX B
Sheet 1 of 2

Date: 5/18/2022 Time: 12:34 User: cemorris Style Table: Langan.stb Layout: Layout1 Document Data: 350035301-SHT-15-EX1.DWG



ADJOINING SUBDIVISION PROPERTY OWNERS

PINE GROVE SUBDIVISION UNIT 2			
BLOCK	LOT	PARCEL ID	OWNER
13	1	R20 222 18 3035 0130 0010	SHELDON AUBREY STRNOUSKY
8	20	R20 222 18 3035 0080 0200	RAFAEL P & MARIN MAYLYN A GODINEZ
8	19	R20 222 18 3035 0080 0190	ELAINE C HUMR LIFE ESTATE
8	18	R20 222 18 3035 0080 0180	KENNETH L & CARRIE LIFE
8	17	R20 222 18 3035 0080 0170	KENNETH & CARRIE LIFE
8	16	R20 222 18 3035 0080 0160	SHERIDAN HARLAN LIFE ESTATE
8	15	R20 222 18 3035 0080 0150	SHERIDAN HARLAN LIFE ESTATE
8	14	R20 222 18 3035 0080 0140	HENRY WILSON
8	13	R20 222 18 3035 0080 0130	VIRGINIA WHITNEY
8	12	R20 222 18 3035 0080 0120	VIRGINIA WHITNEY
8	11	R20 222 18 3035 00800110	VIRGINIA A WHITNEY
8	10	R20 222 18 3035 0080 0100	WALTER & PEARL KING
8	7	R20 222 18 3035 0080 0070	EXEMPT PER PUBLIC RECORD LAWS
8	6	R20 222 18 3035 0080 0060	KIMBERLY A CLAY
8	5	R20 222 18 3035 0080 0050	JOHN F & JOANNE F RAMPINO
8	4	R20 222 18 3035 0080 0040	DARLENE D & CHARLES F CASTANZA
8	3	R20 222 18 3035 0080 0030	TOMMY LEWIS JR
8	2	R20 222 18 3035 0080 0020	MARVIN R & DEBORAH L SEALS
8	1	R20 222 18 3035 0080 0010	MICHAEL CASH
1	62	R20 222 18 3035 0010 0620	JOYCE E THOMPSON
1	61	R20 222 18 3035 0010 0610	TERESA & BRIAN TRITHART
1	60	R20 222 18 3035 0010 0600	LEANDRO ROCHA & JULIA MERK-ROCHA
1	59	R20 222 18 3035 0010 0590	EUGENE CONCALNS SHILOH CONSTRUCTION COR
PINE GROVE SUBDIVISION UNIT 1			
BLOCK	LOT	PARCEL ID	OWNER
1	33	R20 222 18 3025 0010 0330	EDWIN L & BETTY A CREGG TTEE
1	32	R20 222 18 3025 0010 0320	JAMES ANTONELLI & BRIDGET DIERCKS

ENCROACHMENTS

1. FENCE LINE CROSSES NORTHERN PROPERTY LINE.

No.	Description	Date
2	ADDED TREES & CERTIFICATION	9/17/2023
1	ADDED CERTIFICATIONS	8/25/2022

Revisions

LANGAN
Langan Engineering and Environmental Services, Inc.
400 N. Ashley Drive, Suite 2175
Tampa, FL 33602
T: 813.439.6100 F: 813.439.6101 www.langan.com
FL CERTIFICATE OF AUTHORIZATION NO. 00000610 LB0001733 LC26000580

Project: OAK GROUP - PINE CONE STREET
BROOKSVILLE
HERNANDO COUNTY FLORIDA

Drawing Title: ALTA/NSPS LAND TITLE SURVEY

Project No.: 350035301
Date: 04/20/2022
Drawn By: RM/CM
Checked By: BAN

Drawing No.: EX B
Sheet 2 of 3

Date: 9/18/2023 Time: 13:58 User: cemorris Style Table: Langan.stb Layout Layout1 Document Date: 350035301-0401.16.101-01.01