



EVALUATION TABULATION
 PQ# No. 23-T00040/AP Q15
Weeki Wachee Woodlands WM Interconnect
 RESPONSE DEADLINE: October 15, 2024 at 12:00 am
 Report Generated: Wednesday, October 30, 2024

SELECTED VENDOR TOTALS

Vendor	Total
Deeb Construction & Development CO	\$156,684.30

**Erin L Kluis
Briggs**

Digitally signed by Erin L Kluis Briggs
 Date: 2024.10.30 07:45:43 -04'00'

WEEKIN WACHEE WOODLANDS WATER MAIN

Weekin Wachee Woodlands Water Main					Deeb Construction & Development CO	
Selected	Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total
General Conditions						
X	1	Mobilization/Demobilization	1	LS	\$2,500.00	\$2,500.00
X	2	Bond	1	LS	\$0.00	\$0.00
X	3	Insurance	1	LS	\$1,000.00	\$1,000.00
X	4	Maintenance of Traffic	1	LS	\$3,500.00	\$3,500.00
X	5	Survey Layout/As-builts	1	LS	\$2,800.00	\$2,800.00
X	6	Erosion Sediment Control and NPDES Permit	1	LS	\$2,500.00	\$2,500.00

EVALUATION TABULATION
PQu No. 23-T00040/AP Q15
Weeki Wachee Woodlands WM Interconnect

Weekin Wachee Woodlands Water Main					Deeb Construction & Development CO	
Selected	Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total
X	7	Pre/Post Video	1	LS	\$1,713.00	\$1,713.00
X	8	Gopher Tortoise Survey and Permitting	1	LS	\$1,500.00	\$1,500.00
X	9	Gopher Tortoise- Bucket Trapped, Pulled, or Monitored (Up To 2)	2	EA	\$250.00	\$500.00
X	10	Gopher Tortoise Relocation (Up To 2)	2	EA	\$7,500.00	\$15,000.00
Water Main						
X	11	8-Inch PVC C900 DR18 Water Main Pipe Via Open Cut With All Necessary Restraints and Fittings	480	LF	\$70.80	\$33,984.00
X	12	Open Cut and Restore Philatelic Drive	1	LS	\$15,625.00	\$15,625.00
X	13	8-inch Valve/Valve Can, Pad, Locate Wire, Restraints	2	EA	\$4,317.87	\$8,635.74
X	14	8-Inch 45 Degree Bends Including Fittings	3	Ea	\$804.94	\$2,414.82
X	15	8-Inch "T" Including Fittings	1	EA	\$1,325.21	\$1,325.21
X	16	8x2 Reducer Including Fittings	1	EA	\$578.20	\$578.20
X	17	2-Inch Gate Valve Including Fittings	1	EA	\$1,834.20	\$1,834.20
X	18	Connect 8-Inch Water Main to Existing 8-Inch "T" Including Fittings	1	EA	\$1,891.66	\$1,891.66
X	19	6x6 Wet Tap, Connect to Existing 6-Inch Water Main Including Fittings	1	EA	\$8,168.81	\$8,168.81

EVALUATION TABULATION

PQu No. 23-T00040/AP Q15

Weeki Wachee Woodlands WM Interconnect

Weekin Wachee Woodlands Water Main					Deeb Construction & Development CO	
Selected	Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total
X	20	8x6 Reducer Including Fittings	1	EA	\$1,039.98	\$1,039.98
X	21	Install Service Lines Up To Existing Near Side Meter Box	3	EA	\$1,246.68	\$3,740.04
X	22	Install Service Lines Up To Existing Far Side Meter Box	2	EA	\$6,478.96	\$12,957.92
X	23	Remove and Replace Driveway Aprons	4	EA	\$5,000.00	\$20,000.00
X	24	Performance Turf Sod-Match Existing	1	LS	\$8,022.00	\$8,022.00
X	25	Cut and Cap 2-Inch Water Main Abandoned in Place	6	EA	\$80.22	\$481.32
X	26	Install Sample Points	2	EA	\$1,686.20	\$3,372.40
X	27	Perform Testing for FDEP Clearance	2	EA	\$800.00	\$1,600.00
Total						\$156,684.30